

Shriya Construction and Consultancy



Shriya Construction and Consultancy

1133, 3rd Floor, 3rd Stage, B Cross, Yelahanka New Town, Bangalore - 560 064.

L No.	Particulars Of item	Unit	Quantity
1	KSRRB 300-1. Earth work excavation by manual means in Ordinary Soil soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH chapter 3. P No. 143/ Item No. 19.1/ PWD SR 2018-19	CUM	1101.05
2	KSRRMBM2990 Plain cement concrete of mix M10 MIX with crushed stone aggregates 40mm nominal size mechanically mixed, placed in foundation and compacted by vibration including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. p No. 254/ Item No. 34.2/PWD SR 2018-19	CUM	161.67
3	Providing and laying plain/ reinforced cement concrete for side drains using M20 nominal mix concrete with OPC cement @ 300kgs, with 20mm and down size granite metal coarse aggregates @0.69cum and fine aggregates @0.43cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc, complete excluding cost of stell as per MORTH specification NO. 1500, 1700, 2200. Including cost of materials, labour, HOM complete as per specifications. Item No. 37.59.2/ page no:271/PWD SR 2018-19	CUM	312.77
4	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specifications. Specification (I No-28.8.2,P No-229)	TON	17.80
5	Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting, including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc ,complete. (Data Rate)	SQM	818.37
6	Providing and Fixing pre cast covering Slab 250mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc, complete. As per Engineer in charge	SQM	77.55



Handwritten signature and date 12/5/20